

**SURVEY & REMONUMENTATION**

STATE OF MICHIGAN  
COUNTY OF CHARLEVOIX  
RECEIVED FOR RECORD

3-2 OCT 18 1996

LAND CORNER RECORDATION CERTIFICATE 96 SEP 19 PM 4:17  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**  
**Charlevoix**  
(County)

Located In: Corner Code #

*Charles M. Brand*  
REGISTER OF DEEDS

1. Public Land Survey	T 33N R 5W	A-10 ✓
	T 33N R 6W	M-10 ✓
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, **Terry E. Brand**, in a field survey on **June 18**, 19 **96**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

**A-10 1/4 corner common to Section 30, T33N-R5W & M-10 Section 25, T33N-R6W**

1840, Township Lines by John Mullett, Set 1/4 post. Sugar 20" S24°E 16lks. (10.56'), Beech 10" N23°W 19lks. (12.54')  
1884, Co. Surveyor E.K. Robinson (Co. Survey bk. pg. 349), Fd. & Set New 3" Cedar Post. Sugar 20" S24°E, 16lks. (10.56'), Beech 10" N23°W 19lks. (12.54')  
1900±, Surveyor Unknown. Co. Survey bk. 119 pg. 25 copy of GLO notes along w/ New Accessories, Sugar 12" N43 1/2°W 52lks. (34.65'), Beech 12" S31 1/2°W 64lks. (42.24')

1908, Co. Surveyor E.A. Robinson, Shows 1/4 cor. on Minutes of Hwy. Survey &, Co. Survey bk. pg. 348 as an 3/4"x6" or 7" Iron Pipe. Sugar 16" N43 1/2°W 52 1/2 lks. (34.65'), Beech 14" S31 1/2°W 64lks. (42.24')

1962, R. Kent (MI Hwy. Dept., Drawing), Fd. 3/4" pipe. 8" Maple S58°E 31.36', 8" Maple S80°E 21.92', 5" Apple N67°E 35.56'

1969, Co. Surveyor Mary Feendt, Shows 1/4 corner on Survey Drw., No descr. or No accessories. Fd. 3/4" Iron Pipe

1976, Granger Engineering Inc., Fd. 3/4" Iron Pipe Certificate of Survey. Liber 238 Page 800. MSHD tag 8" Maple S58°E 31.36', tag 8" Maple S80°E 21.92', Fences South-West

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

**A-10 1/4 corner common to Section 30, T33N-R5W & M-10 Section 25, T33N-R6W**

Fd. 3/4" x 7" iron pipe

Falls 0.5' West of North-South fenceline

Fd. nail & tag(MSHD) in 8" Maple stump, S75°E, 21.94'

Fd. nail & tag(MSHD) in 9" Maple, S50°E, 31.34'

Charlevoix Co. Surveyor  
**APPROVED**  
Signature *Mary C. Feendt*  
Date: 12-29-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**A-10 1/4 corner common to Section 30, T33N-R5W & M-10 Section 25, T33N-R6W**

Fd. 3/4" x 7" iron pipe, Replaced with 3" cast iron Charlevoix County Monument

Falls 0.5' West of North-South fenceline

Fd. nail & tag(MSHD) in 9" Maple, S50°E, 31.34'

Set nail & tag in 4" Ash, N54°E, 35.40'

Set nail & tag in 8" Tw. Maple, S76°E, 37.58'

Set nail & tag in 24" Maple, N87°W, 209.51'(EDM)

Found corner is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by *Terry E. Brand*

Date 8-29-96

Surveyor's Michigan License No. 33969

LIBER **003** PAGE **20**

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983