

FEB 22 2001

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX
RECORDED BOOKS

96 DEC 11 PM 3:11

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Charlevoix

Charles M. Chamberlain
REGISTER OF DEEDS

	Located In:	Corner Code #
1. Public Land Survey	T 32N R 7W	M-1
	T 32N R 6W	A-1
	T 33N R 6W	A-13 ✓
	T 33N R 7W	M-13
2. Property Controlling in Section	S ___ T ___ R ___	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	I
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Wayne E. Boss, in a field survey on OCTOBER 14, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | | | |
|-----|---|--|--|
| M-1 | GLO JUNE 1839
JOHN HODGSON
SET POST AT INTER-SECTION COR. TWP. 32 & 33 N., 6 & 7 W.
1. BEECH 7 N35W 23 LKS.
2. BEECH 7 S74W 18 LKS. | FD. TWP. COR.
1. BEECH 9 N41W 23 LKS.
3. SUGAR 8 S8E 4 LKS.
E.K. ROBINSON REUSED COR. IN LATER SURVEY. NO DATE GIVEN. ALSO E.K.R. USED COR. IN 1886 | 1/4" SOLID ROD SET BY UNKNOWN.
L.FEINDT USED IN 1978 SURVEY AND 1986 SURVEY.
4. N60E 90.0' 20" MAPLE
5. N20W 59.0' P.P.
6. WEST 33.0' T-IRON |
| | JUNE 1877 E.K. ROBINSON | | 1/2" IR. & CAP SET BY J. FERGUSON
7. PWR. POLE S26E 88.78'(SEE BACK) |


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-1 1/2" IRON FOUND WITH CAP(FERGUSON & CHAMBERLAIN). NO DIRECT TIE TO GLO.
4. N60E 90.0' 28" MAPLE
6. WEST 32.63' T-IRON FD.
7.PWR. POLE S26E 88.78'
8. 12" APPLE S66W 100.30'
9. TELE. BOX N10W 60.35'
10. ROAD SIGN N80E 41.26'

Charlevoix Co. Surveyor
APPROVED
Signature *Mary C. Feinath*
Date: *Nov. 13, 1996*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-1 & M-13 TOWNSHIP CORNER COMMON TO M-1 T32N-R7W & M-13 T33NN-R7W & A-1 T32N-R6W & A-13 T33N-R6W.
CHARLEVOIX CO. MON. SET
4. N60E 90.2' 28" MAPLE (SPIKE & TAG SET)
6. WEST 32.63' T-IRON FOUND
7. S26E 88.78' POWER POLE SPIKE FOUND
8. 12" APPLE S66W 100.30'
9. N10W 60.48' CTR. OF TELE. RISER
10. N70E 24.5' AT SIGN POST
AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.



Signed by _____ Date 11 / 2 / 96
Surveyor's Michigan License No. 20703 LIBER 003 PAGE 85

This should have been entered