FEB 0 4 1999

STATE OF MICHIGAN COUNTY OF CUIVER FUNCTIONS RECEIVED FULL LEGERD.

SECTION

SECTION	98	DEC I	7 P	M 5: C	12		
LAND CORNER RECORDATION CERTIFI	ICATE					:	
Filing Requirement of Act 74, Mich. P.A. For corners in	. 1970	. /-	ک والاناسر	72 1	,		
For corners in		REGIST					
CHARLEVOIX Located In: Corner Code #	'	120101		55550			
(County)	-					,	٠.
1. Public Land Survey T 33NR 7W A-4		•					١.
TR		e e e	· · ·				
<u> </u>		1.	1		, .		
T R 2. Property Controlling S T R			a a S				
in Section ST_R	7						
3. Miscellaneous S T R				4		'	,
Property in Sec. S T R		Registe	er of D	eeds St	amp 8	. File N	lumb
				1.0			
4. Lot No , Recorded Plat	_						
5. Private Claims	1	A B C	D	E F (Э Н 	1 1	K
	2		\$	 	 \$-		
	3			- -		+	
I, ARTHUR R. RANGER , in a field survey on AUG. 11 , 19 98	<u>3</u> · 4		§		10-	11-	
do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manu	lin ual ⁵						
of survey instructions of the United States Department of the Interior, Bureau of Land Management or by	ya . 6	—18—	17	16-	15-	14-	
decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Lav			-			+	+-
established, re-established, monumented, recovered, found as expressed below:	8	19	20	21_	22-	23	2
NOTE: Not more than 2 corners, all in the same town and range, may be recorded	9.					1	-
on this certificate.	10	30	1 29	28	27_	26-	2
	11			-			_
	.12	31	32	33	34-	35	:
	13			<u> </u>		<u> </u>	
A. Description of original monument and accessories and/or subsequent restoration:	÷						
A-4 Qr. Corner common to Sec. 12, T.33N., R.8W., & Sec. 7, T.33N., R.7W. 1840-GLO surveyor John Mullett said that a 20" Cedar was the Qr. Sec. Corner—no witnesses	2 .		,				
1883- William Miller used the corner in a survey of Sec. 12, T.33N., R.8Wno witnesses.			•				
1975- Wayne Boss found a 2" iron pipe during his survey and witnessed: spike in P.P. N75°W 32.65'; W. Edge of 12" culvert S55°W 44.0'; E. Edge of 12" culvert S01°W 29.0'	/ 73.25'; sp	ike in 5	" Popia	r South	ı İ	,	
1978- John E. Ferguson found a 1-1/4" iron pipe during his survey and witnessed: 5" Poplar SC	03°E 33.7	2'; 4" P	oplar S	55°E 6	9.2',		
F.E. post N33°E 29.25'			-		11		
1978- John E. Ferguson recorded an LCRC on the corner L.02, Pg. 80witnesses are the sam	ne as abov	e.				1	
B. Description of corner evidence found and/or method applied in restoring or reestablishing of	corner:				:		•
A-4 Qr. Corner common to Sec. 12, T.33N., R.8W., & Sec. 7, T.33N., R.7W. 1998- Arthur R. Ranger found a 1/2" iron rod and some of the witnesses of record. The corner	r fite line a	nd dista	nca fro	m acce	nted c	ornere	
To the North.	, 1110 1110 (1	ia aiota	.100 110	'	picu o	OTTICIS	
C. Description of monument for corner and accessories established to perpetuate locating the	nocition o	f'thaiaa	tnor.		1 1 1		
A-4 Qr. Corner common to Sec. 12, T.33N., R.8W., & sec. 7, T.33N., R.7W.	position o	i uie co	me.				
(Replaced with a Charlevoix County Monument) Witnesses:	C	harlev	oix C	o. Su	rvey	or ·	,
1/2" iron rod West 33.18'				OVE		•	
5" Popiar S43°E 72.58'	Sign	ature			Fl	milt	4
12" W. Pine N55°E 62.65' 12" W. Pine N04°W 93.00'	C.g.	Date	9: N	N.12.	1999	1	
	1	-				. '	
AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION	OF THE	ORIGIN.	AL CO	RNER.			•
$I \rightarrow I$							
Signed by # Date Date	10/13/9	8	-4	٠.		,	
Surveyor's Michigan License No. 31601							
	:						1 2
FORM APPROVED BY	Y MICHIGAN S	TATE BOAF	RD OF PRO	DFESSION/	ALSURVI	EYORS JA	N. 28. 1
		's ,	r i i		1.1	VISED MA	

