

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

96 DEC 11 PM 3:00

corners in
Charlevoix

(County)

Located in:

Corner Code #

Public Land Survey

T 32N R 7W

B-1

T 33N R 7W

B-13

Property Controlling

S

T

R

In Section

S

T

R

Miscellaneous

S

T

R

Property in Sec.

S

T

R

REGISTER OF DEEDS

SURVEY &
REMONUMENTATION


FEB 19 1998

Register of Deeds Stamp & File Number

Lot No. Recorded Plat

Private Claims

SECTION



Wayne E. Boss in a field survey on OCTOBER 21, 1996, hereby certifies that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the recent manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as pressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

- B-1 GLO JUNE 1839 WILLIAM MILLER OCT. 1883 1/4" PIPE SET BY UNKNOWN. USED BY NICK DEYOUNG IN 1980 AND SUBSEQUENT SURVEYS.
- JOHN HODGSON FOUND 1/4 POST
- SET 1/4 SEC. POST 3. BIRCH 24 S9E 10
- 1. B1 ASH 7 N17W 5 4. HEMLOCK 30 S7W 82
- 2. B1 ASH 7 N37E 15
- E.A. ROBINSON FD. 1/4 POST IN LATER SURVEY. NO NEW WIT.
- 5. N75W 24.4' 14" MAPLE
- 6. S72W 53.90' POWER POLE
- 7. N8W 21.30' 16" MAPLE
- 8. N82E 33.85' 3" CEDAR

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- B-1 1/4" PIPE FOUND NORTH OF THE TRAVELED ROAD.
- 5. N75W 25.35' TWIN 18" MAPLE
- 6. S72W 55.48' POWER POLE
- 7. N08W 20.82' 16" MAPLE
- 8. N82E 32.95' 6" CEDAR

Charlevoix Co. Surveyor
APPROVED
Signature Wayne E. Boss
Date: Nov 13, 1996

Description of monument for corner and accessories established to perpetuate localizing the position of the corner:

- B-1 & B-13 B-1 T32N-R7W CORNER COMMON TO B-13 T33N-R7W.
- CHARLEVOIX CO. MON. SET. NEW SPIKES AND TAGS SET AT ALL WITNESSES.
- 5. N75W 25.35' TWIN 18" MAPLE
- 6. S72W 55.48' POWER POLE
- 7. N08W 20.82' 16" MAPLE
- 8. N82E 32.95' 6" CEDAR

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER



Recorded by Wayne E. Boss
Surveyor's Michigan License No. 20703 LIBER 0113 PAGE 74