

FEB 19 1998

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX
REGISTER OF DEEDS

96 DEC 11 PM 3:04

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Charlevoix


Located in: Corner Code #

1. Public Land Survey	T 32N R 7W	G-1
	T 33N R 7W	G-13
	T R	
	T R	
2. Property Controlling In Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Charles B. Boss
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

1. Lot No. _____, Recorded Plat _____
2. Private Claims _____



Wayne E. Boss, in a field survey on OCTOBER 17, 1996, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

O.T.E.: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

G-1	GLO JUNE 1839 JOHN HODGSON CORNER IN LAKE SET POST 1 CHAIN WEST A. IRONWOOD 8 S39W 20 B. CEDAR 9 N51W 14	AUG. 1944 R.F. SLOAN REFERENCED CORNER LOCATION TO A MON. 120 FT. WEST ON N. SEC. LINE AND TO A MON. 120 FT. SOUTH ON E. SEC. LINE, SEC. 4 CORNER LOCATION NO LONGER UNDER WATER BECAUSE OF LOWERED LAKE LEVEL.	M. FEJNDT SET IR. AT CORNER (G-1) FOR CHALET VILLAGE SUBDIVISION L.2 PAGE 292, MAR. 1976 1. WEST 120.0 CONC. MON. 2. WEST 10.0 CONC. MON. 3. SOUTH 120.0 1/2" IRON
-----	---	---	---


Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-1 NO CORNER FD. AT LOCATION PER CHALET VILLAGE SUB. PLAT MONS. WERE FOUND WHICH REFERENCE SEC. CORNER LOCATION. CORNER RESET BASED ON MONUMENTS.
1. WEST 120.0' CONC. MON.
2. WEST 10.0' CONC. MON.

Charlevoix Co. Surveyor
APPROVED
Signature *Mary C. Fejndt*
Date: *Nov. 13, 1996*

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-1 T32N-R7W CORNER COMMON TO G-13 T33N-R7W
CHARLEVOIX COUNTY MON. SET
1. WEST 120.0' CONC. MON.
2. WEST 10.0' CONC. MON.
3. S30W 28.95' N.E. COR. HOUSE
4. S60W 43.80' N.W. COR. HOUSE
5. EAST 21' LAKE CHARLEVOIX
6. NORTH 10' LAKE CHARLEVOIX



THIS POSITION NOT ESTABLISHED BY ORIGINAL GOV'T SURVEYORS. THIS MONUMENT IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.

Recorded by *Wayne E. Boss* Date *11/23/96*
Surveyor's Michigan License No. *20703* LIBER *003* PAGE *79*