

SURVEY & REMONUMENTATION

Sheet 15 of 17 sheets

FEB 19 1998

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX

96 DEC 11 PM 3:08

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION
for corners in
Charlevoix
(County)

Located In: Corner Code #

Public Land Survey	T 32N R 7W	J-1
	T 33N R 7W	J-13
	T R	
	T R	
Property Controlling in Section	S T R	
Miscellaneous	S T R	
Property in Sec.	S T R	

Chamberlain D. Chamberlain
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Lot No. _____ Recorded Plat _____
Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	14	15	16	17	18							
7													
8	19	20	21	22	23	24							
9													
10	25	26	27	28	29	30							
11													
12	31	32	33	34	35	36							
13													

Wayne E. Ross, in a field survey on OCTOBER 22, 19 96, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the present manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as pressed below:

O.T.E.: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

- | | | | |
|-----|--|--|---|
| J-1 | GLO JUNE 1839
SET 1/4 SECT. POST
1. BEECH 18 N30E 36
2. BEECH 6 N16W 18 | MAY 1886
E.K. ROBINSON
SET NEW N 1/4 STAKE
NO WIT. OR COR. FD.
3. SUGAR 20 N52 1/4 E 35 1/4 LKS.
4. BEECH 6 S11 1/4 E 28 1/4 LKS. | S. CHAMBERLAIN DEC. 1981
SET CHARL. CO. MARKER IN PILE OF ROCKS MIDWAY BETWEEN SECTION CORNERS.
5. N62E 35.04' 30" MAPLE
6. N76E 68.85' 7" MAPLE |
|-----|--|--|---|


Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- J-1 NO MON. OR WITS. FOUND. NEW CORNER SET MIDWAY ON LINE BETWEEN SECTION CORNERS. DISTANCES MATCH CHARLEVOIX ABSTRACT & ENGINEERING'S LOCATION.

Charlevoix Co. Surveyor
APPROVED
Signature: *Mary G. Ferritt*
Date: 11/29/96

Description of monument for corner and accessories established to perpetuate locating the position:

- J-1 & J-13 J-1 T32N-R7W CORNER COMMON TO J-13 T33N-R7W
CHARLEVOIX CO. MON. SET
7. 587E SPIKE & TAG SET IN 8" POPLAR 153.07'
8. 360E SPIKE & TAG SET IN TWIN 8" POPLAR 97.37'
9. N 63W SPIKE & TAG SET IN FENCE POST 18.44'
10. N15E SPIKE & TAG SET IN FENCE COR. POST 10.90'



AND IS ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

Surveyed by *Wayne E. Ross* Date 11/29/96
Surveyor's Michigan License No. 20703 LIBER 003 PAGE 82