

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX
REGISTERED FOR 1998

96 DEC 11 PM 3:10

Charles M. Clumber
REGISTER OF DEEDS

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

or corners in
Charlevoix
(County)

Located in:

Corner Code L-1

Public Land Survey

T 32N	R 7W	L-1
T 33N	R 7W	L-13
T	R	
T	R	

Property Controlling
In Section
Miscellaneous
Property in Sec.

S	T	R	
S	T	R	
S	T	R	
S	T	R	

SURVEY &
REMONUMENTATION

FEB 19 1998

Register of Deeds Stamp & File Number

SECTION

Lot No. _____, Recorded Plat _____
Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2												
3												
4												
5												
6												
7												
8												
9												
10												
11												
12												
13												

Wayne E. Boss in a field survey on OCTOBER 14, 19 96, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned lines 1 and 2 above were in conformance with regulations and rules therefore as required in the present manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as pressed below:

DTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

L-1	GLO JUNE 1839 JOHN HODGSON SET 1/4 SEC. POST 1. BIRCH 8 N28E 20 2. BIRCH 16 N74W 34	JUNE 1886 E.K. ROBINSON FD. 1/4 POST NO NEW WIT.	MAY 1978 LAWRENCE FEINDT SET CHARL. CO. MON MIDWAY BETWEEN SEC. CORNERS LCRC L.2 P.71 (CORRECTED OCT. 1983 & AGAIN IN FEB 1986) 3. N75E 20.70' 5" MAPLE 4. S40E 9.09' 5" MAPLE 5. N45W 17.28' 12" MAPLE 6. WEST 6.45' 3" MAPLE	7. EAST 40.16' FENCE LINE
-----	---	---	--	---------------------------

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-1	FD. CHARL. CO., MON 4. S40E 9.09' 5" MAPLE 5. N45W 17.28' 16" MAPLE 6. WEST 6.45' 3" MAPLE 7. EAST 40.16' FENCE LINE	NO DIRECT TIE TO GLO
-----	--	----------------------

Charlevoix Co. Surveyor
APPROVED
Signature Wayne E. Boss
Date: Nov. 19, 1996

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-1 & L-13 L-1 T32N-R7W CORNER COMMON TO L-13 T33N-R7W
CHARL. CO. MON.FD.
4. S40E 9.09' 5" MAPLE (NEW SPIKE & TAG SET AT 9.25')
- 5. N45W 17.28' 16" MAPLE (NEW SPIKE & TAG SET AT 17.06')
- 6. WEST 6.45' 3" MAPLE
- 7. EAST 40.16' FENCE LINE
- 8. WEST 31.72' 10" MAPLE SPIKE & TAG SET
- 9. S10E 21.18' 12" MAPLE SPIKE & TAG SET



AND IS ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

Surveyor's Michigan License No. 20703 Date 11/29/96 Page 84