

REVISED

99 OCT 22 AM 10:40

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

*Charles W. Feindt*

REGISTER OF DEEDS

For corners in  
Charlevoix

(County)

Located In:

Corner Code #

- 001

- Public Land Survey

T 33N R 7W

MC WEST I-13

T R

T R

T R

T R

- Property Controlling  
In Section

S

T R

S T R

- Miscellaneous  
Property in Sec.

S

T R

S

T R

RECORDED

FEB 01 2000

SECTION

Register of Deeds Stamp & File Number

- Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
- Private Claims \_\_\_\_\_

Wayne E. Boss, in a field survey on JULY, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, covered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Description of original monument and accessories and/or subsequent restoration:

M.C. BETWEEN I-1 & H-1

NO OTHER CORNER  
RECORD OR CORNER  
LOCATION FOUND.

GLO JUNE 1839

JOHN HODGSON

EAST MARGIN OF A LAKE

A CEDAR 14 IN DIAMETER

FOR MEANDER POST

MAY 1947, MARY FEINDT FOUND OLD E-W FENCE  
AND PLACED IRONS ON WESTERLY EXTENSION

JAN. 1998, FERGUSON & CHAMBERLAIN, ASSOC. USED IRON PIPES AS FOUND ALONG  
SOUTH LINE OF SECTION 34, T33N, R7W

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M.C. NO EVIDENCE FOUND. CORNER LOCATION SET ON ESTABLISHED SECTION LINE AT GLO DISTANCE OF 1617 FT. DISTANCE FELL ON TOP OF BANK WHICH IS WHERE THE MEADNER CORNER MOST PROBABLY WOULD HAVE BEEN SET.

PREVIOUS MEANDER CORNER SET ADJUSTED NORTH TO FIT SECTION LINE FROM PRIOR MARY FEINDT SURVEY AND USED BY FERGUSON & CHAMBERLAIN, ASSOC. IN JAN. 1998 SURVEY.

Charlevoix Co. Surveyor

APPROVED

Signature *Mary C. Feindt*

Date: *Oct 21 1999*

*Aug. 19, 1999*

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M.C. BETWEEN I-13 AND H-13 T33N-R7W

CHARLEVOIX CO. MON. RESET

1. S.E. COR. OF NEW ADDITION TO HOUSE N60W 44.34"

2. 10" CEDAR S17E 19.78' ADJUSTED NAIL & TAG

3. C/L DRIVE NORTH 6'

4. WEST TO WATERS EDGE 153'

5. 12" CEDAR S82W 32.33' SET NAIL & TAG



Signed by *Wayne E. Boss*

Date *Sept. 23, 1999*

Surveyor's Michigan License No. 20703