

T33NR9W (M-13) is the
SAME CORNER AS T33N8W (A-13)

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX
RECEIVED

99 DEC 20 PM 2: 12

For corners in

Charlevoix

(County)

Located In:

Corner Code #

1. Public Land Survey

T 33NR 8W

A-13 ✓

T R

T 32NR 8W

A-1

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

Charles B. Justice

REGISTER OF DEEDS

RE

FEB 2000

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Wayne E. Boss

DECEMBER 99

I, _____, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-13 JUNE 5, 1839

JOHN HODGSON, DEPUTY SURVEYOR
ESTABLISHED TOWN CORNER POST
BEECH 16 INCH N53°W 11 LINKS
BEECH 12 INCH N70°E 18 LINKS

MARCH 26, 1964

MATT A. KOVISTO,
SURVEY CHIEF MICH.ST.HWY.DEPT.
FD. BOTTOM OF OLD POST & STONE
NEXT TO POST,
PLACED 2"x3' AXLE SHAFT
9" ELM N85°W 72.46'
7" ELM NORTH 77.58'

FEB.7,1972 & JULY 31, 1987

MC FEINDT, RLS
FOUND 2" AXLE SHAFT
AT FENCE INTERSECTION
SEP. 14, 1989, NB DEYOUNG, RLS
FD. 2" AXLE SHAFT
6" MAPLE N. 67.00', 4" APPLE N20°W
7.20', 6" PINE S70°W 30.40'
6" PINE S15°W 21.30'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-13 DECEMBER 8, 1999

FOUND 2" AXLE SHAFT
AT FENCE INTERSECTION
12" MAPLE NORTH 67.00'
4" APPLE N20°W 7.20'
12" RED PINE S70°W 30.40'
12" RED PINE S15°W 21.30'
B-13 TO A-13 GLO 41 CHAINS (2706') MEASURES 2695.22'
A-13 TO L-13 GLO 40 CHAINS (2640') MEASURES 2603.89'

Charlevoix Co. Surveyor
APPROVED
Signature *Mary C. Feindt*
Date: DEC. 16, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-13 PLACED CHARLEVOIX COUNTY STEEL MARKER

12" MAPLE N10°E 67.24' SET NAIL & TAG
12" RED PINE S85°W 30.63' SET NAIL & TAG
12" RED PINE S33°W 21.57' SET NAIL & TAG
6" RED PINE S47°E 36.63' SET NAIL & TAG

AND IS ACCEPTED AS A CAREFUL & FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER

Signed by

Surveyor's Michigan License No.

20703

Date



LIB 003 PAGE 299