

99 DEC 20 PM 2:13

*Charlene M. Neutong*  
 REGISTER OF DEEDS

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Charlevoix

(County)

Located In:

Corner Code #

1. Public Land Survey

T 33NR 8W B-13 ✓  
 T R  
 T 32NR 8W B-1  
 T R

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Wayne E. Boss

DECEMBER 99

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

<p>B-13 JUNE 5, 1839                  JOHN HODGSON, DEPUTY SURVEYOR                  SET ¼ SECTION POST                  BEECH 14 INCH N46°E 34 LINKS                  BEECH 14 INCH N78°W 28 LINKS</p>	<p>FEB. 8, 1972 MARY FEINDT PLACED                  IRON AT ¼ POST BY PRORATION                  OCT. 23, 1974 LR FEINDT FD. BENT IRON                  REPLACED WITH CONCRETE MONUMENT                  POWER POLE N10°E 39.10',                  12" MAPLE S68°W 26.55'                  30" W.ASH S82°E 29.48'</p>	<p>FEBRUARY 7, 1989,                  NB DEYOUNG, RLS                  FD. CONC. MONUMENT                  POWER POLE NORTH 39.05'                  4" POPLAR SOUTH 13.60'                  12" MAPLE S50°W 26.00'                  4" POPLAR EAST 7.95'</p>
---	---	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-13 DECEMBER 8, 1999  
 FOUND CONCRETE MONUMENT  
 POWER POLE N10°E 39.10' NAIL & TAG IN S. FACE  
 18" MAPLE S68°W 26.55' NAIL & TAG COVERED OVER  
 36" ASH S82°E 29.48' NAIL & TAG COVERED OVER  
 DEAD 4" POPLAR SOUTH 13.60' FD. NAIL & TAG NBD  
 6" POPLAR EAST 7.95' FD. NAIL & TAG NBD  
 C-13 TO B-13 GLO 40 CHAINS (2640') MEASURES 2625.74'  
 B-13 TO A-13 GLO 41 CHAINS (2706.0') MEASURES 2695.23'

Charlevoix Co. Surveyor  
**APPROVED**  
 Signature *Mary C. Feindt*  
 Date: Dec 16, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-13 CONCRETE MONUMENT IN PLACE WITH OLD CAP 3920 (MC FEINDT)  
 POWER POLE N07°E 39.53' SET NAIL & TAG  
 18" MAPLE S77°W 26.50' SET NAIL & TAG  
 36" ASH S58°E 29.63' SET NAIL & TAG  
 6" POLAR N87°E 8.15' SET NAIL & TAG

AND IS ACCEPTED AS A CAREFUL & FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER

Signed by \_\_\_\_\_  
 Surveyor's Michigan License No. 20703

Date \_\_\_\_\_



LIBER 003 PAGE 300