

99 SEP 16 PM 2:25

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Charles B. Justice

For corners in

Charlevoix

(County)

Located in:

Corner Code #

1. Public Land Survey

~~33~~N R 8W

E-13 ✓

T R

~~32~~N R 8W

E-1

T R

2. Property Controlling
 in Section

S T R

3. Miscellaneous
 Property in Sec.

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Wayne E. Boss

MAY 1999

I, _____, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

REGISTER OF DEEDS

SECTION

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	H
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

E-13	MAY & JUNE 1839	JUNE 1, 1972	AUGUST 15, 1972
	JOHN HODGSON, DEPUTY SURVEYOR	MARY C. FEINDT, P.S.	CG OSTLING, P.S.
	SET SECTION CORNER POST	FOUND IRON	FD. 3/4" PIPE
	BEECH 10 INCH N29°E 33 LINKS	NO WITNESSES	8" PEACH TREE N32°E 37.05'
	BEECH 10" N3°W 17 LINKS		8" MAPLE S48°W 50.55'
	MARCH 1880, JOS. R. DIXON, DEPUTY SURVEYOR		
	FD. SECTION POST & WITNESSES		

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


E-13 MAY 1999
 FOUND 1 3/4" PIPE AT ROAD BEND 36'+/- NW OF CL & TREE LINE TO NORTH
 8" MAPLE S50°W 50.34' WITH BLAZE ON NE FACE
 F-13 TO E-13 GLO 40 CHAINS (2640') MEASURES N87°47'54"W 2610.11'
 E-13 TO D-13 GLO 40 CHAINS (2640') ACROSS SMALL LAKE, MEASURES N87°19'05"W 2613.93'

Charlevoix Co. Surveyor
 APPROVED
 Signature *Mary C. Feindt*
 Date: *Aug 19, 1999*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13 PLACED CHARLEVOIX COUNTY STEEL MARKER
 8" MAPLE S50°W 50.34' SET NAIL & TAG
 8" MAPLE S82°W 28.39' SET NAIL & TAG
 12" LOMBARDI POPPLER N8°E 11.79' SET NAIL & TAG
 3" CHERRY N45°E 67.60'

AND IS ACCEPTED AS A CAREFUL & FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER



Signed by *Wayne E. Boss*
 Surveyor's Michigan License No. 20703

Date 8/23/99

LIBER 003 PAGE 259