

99 SEP 16 PH 2:23

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

*Charles M. [Signature]*

REGISTER OF DEEDS

For corners in

Charlevoix

(County)

Located In:

Corner Code #

1. Public Land Survey

T33N R 8W

G-13 ✓

T R

B2N R 8W

G-1

T R

2. Property Controlling  
 in Section

S T R

S T R

3. Miscellaneous  
 Property in Sec.

S T R

S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Wayne E. Boss

APRIL 1999

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

A. Description of original monument and accessories and/or subsequent restoration:

|      |   |  |
|------|---|--|
| G-13 | MAY & JUNE 1839   | JAN. 11, 1899, DEC. 12, 1899                             |
|      | JOHN HODGSON, DEPUTY SURVEYOR   | DC NETLETON, DEPUTY SURVEYOR                             |
|      | SET SECTION CORNER POST   | FD. GLO POST AND BEARING TREES MADE BY F. CHURCH SURVEYO |
|      | BEECH 7 IN N6*E 15 LINKS  | BEECH 12 INCH S58*W 60 1/2 LINKS                         |
|      | SUGAR 8 INCH N58*W 15 LINKS   | MAPLE 17 INCH N17*W 14 1/2 LINKS                         |
|      | AUGUST 16, 1990 A. LENNOX, P.S.                                       |  |
|      | SET IRON AT GLO POSITION  |  |
|      | 8" IRONWOOD N80*W 17.2', 12" MAPLE S45*E 14.0', 20" MAPLE S15*E 12.4" |  |

Charlevoix Co. Surveyor

APPROVED

Signature *Mary C. [Signature]*

Date: *Aug 19, 1999*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-13 APRIL 21, 1999  
 FOUND 1/2" IRON WITH CAP 20357-25873 ON OLD N-S FENCE AND REMAINS OF FENCE TO EAST-WEST  
 8" IRONWOOD N66\*W 17.20' FOUND BLAZE  
 12' MAPLE S44\*E 13.98' FOUND BLAZE  
 20" MAPLE S10\*E 12.83' FOUND BLAZE  
 H-13 TO G-13 GLO 40 CHAINS ( 2640') N88\*26'09"W 2613.04'  
 G-13 TO F-13 GLO 40 CHAINS (2640'), MEASURES N88\*11'56"W 2618.24'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13 CHARLEVOIX COUNTY STEEL MARKER  
 8" IRONWOOD N66\*W 17.20' SET NAIL & TAG  
 12" MAPLE N27\*E 13.75' SET NAIL & TAG  
 12" MAPLE S44\*E 13.98' SET NAIL & TAG  
 20" MAPLE S10\*E 12.83' SET NAIL & TAG

AND IS ACCEPTED AS A CAREFUL & FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER

Signed by \_\_\_\_\_

Surveyor's Michigan License No. 20703

Date \_\_\_\_\_

