

99 OCT 22 AM 10:39

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

*Wayne E. Boss*  
REGISTER OF DEEDS

For corners in

Charlevoix

(County)

Located In:

Corner Code #

1. Public Land Survey

T 33R 8W

K-13 ✓

T R

K-1

T 32R 8W

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

RF  
2001

SECTION

Register of Deeds Stamp & File Number

1. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
2. Private Claims \_\_\_\_\_

Wayne E. Boss

SEPTEMBER 99

\_\_\_\_\_ in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, discovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Description of original monument and accessories and/or subsequent restoration:

K-13 MAY & JUNE 1839

JOHN HODGSON, DEPUTY SURVEYOR  
SET POST

CEDAR 19 N39\*W 19 LINKS  
LYNN 9 INCH N21\*E 10 LINKS

JUNE 24, 1922, R.F.SLOAN, ENGINEER

FD. ORIGINAL SEC. CORNER  
PLACED IRON PIN AT CORNER  
NO WITNESS NOTED

NOV. 1979 W.E.BOSS FD. T-IRON

DEC. 30 1982

L.R. FEINDT, P.S.  
PERFORMED SURVEY IN  
SECTION 35, T33N, R8W  
DID NOT FIND SE SEC. COR.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-13 DECEMBER 17, 1998

FOUND T-IRON IN CENTER OF MCCRACKEN ROAD AND IN LINE WITH OLD FENCE TO WEST  
FOUND 2" x 18" PIPE LAYING ON SURFACE ABOUT 6' NORTH OF T-IRON

12" CEDAR WEST 47'+/- WITH OLD BARBED WIRE TO WEST & EAST  
7" CEDAR S45\*W 13.44' FOUND BLAZE ON NE FACE

16" BASSWOOD S87\*W 24.36' FOUND BLAZE ON NE FACE

8" CEDAR N46\*W 21.38' FOUND BLAZE ON SE FACE

6" CEDAR N36\*E 25.68' FOUND BLAZE SW FACE

L-13 TO K-13 GLO 40 CHAINS (2640') MEASURES S88\*08'21"E 2604.92'

K-13 TO J-13 GLO 40 CHAINS (2640') RF SLOAN 2607' MEASURES 2604.12'

Charlevoix Co. Surveyor

APPROVED

Signature *Wayne E. Boss*

Date: *Aug 19, 1999*

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13 PLACED CHARLEVOIX COUNTY STEEL MONUMENT

7" CEDAR S45\*W 13.44' SET NAIL & TAG

16" BASSWOOD S87\*W 24.36' SET NAIL & TAG

8" CEDAR N46\*W 21.38' SET NAIL & TAG

6" CEDAR N36\*E 25.68' SET NAIL & TAG

AND IS ACCEPTED AS A CAREFUL & FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER

signed by *Wayne E. Boss*  
Surveyor's Michigan License No. 20703

Date *Sept 23, 1999*

