

FEB 22 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX
REGISTERED DEEDS

00 DEC 21 AM 9:04

Charles B. Neering
REGISTER OF DEEDS

For corners in

Charlevoix	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 33N R 8W	E-6
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Wayne E. Boss, in a field survey on November, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17	•	16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
 E-6 October 22, 1841 Charles W. Cathcart, D.S.
 Found Hemlock 24" tree at location
 Used as 1/4 post
 September 6, 1973 M.C. Feindt, P.S.
 Found 1" pipe in C.L. traveled track
 3) 12" Elm N50°W 65.90'
 4) 14" Elm N40° E 39.60'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 E-6 October and November 2000
 No evidence of old corner was found, as also no old witnesses were found.
 1/4 corner reset at mid point between section corners E7 & E5
 Some evidence of old fence on ground was found to North
 New corner fell 7' North of center line of East-West gravel road

E-7 to E-6 GLO 40 chains (2640') measures N01° 27'08"W 2654.615'
 E-6 to E-5 GLO 40 chains (2640') measures N01° 27'08"W 2654.615'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 E-6 Placed Charlevoix County steel marker set midway on line between E5 & E7
 5) 6" x 8" guard rail post N 70° W 66.77' placed nail in top
 6) 22' cedar N 23° W 54.50' placed nail in East face
 7) 16" red pine N 37° E 41.76' placed nail in West face
 8) Power pole S 9° W 100.55' placed nail in West face

Charlevoix Co. Surveyor
 APPROVED
 Signature *Mary C. Feindt*
 Date *12/20/2000*

And is accepted as a careful and faithful reestablishment of the position of the original corner.

Signed by _____ Date 12/15/2000
 Surveyor's Michigan License No. 20703

