

99 DEC 20 PM 2:11

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Charlene M. Justice
 REGISTER OF DEEDS

For corners in

Charlevoix
 (County)

Located In:

Corner Code #

- | | | |
|------------------------------------|-----------|---------------|
| 1. Public Land Survey | T33N R 9W | <u>L-13</u> ✓ |
| | T R | |
| | T32N R 9W | L-1 |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |

REGISTER OF DEEDS

FEB 01 2000

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Wayne E. Boss DECEMBER 99
 in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- | | | |
|--|---|---|
| L-13 JUNE 5, 1839
JOHN HODHSON, DEPUTY SURVEYOR
SET 1/4 POST
BLACK ASH 16 INCH N13°W 20 LINKS
SUGAR 10 INCH N42°W 25 LINKS
APRIL 1884
FL CHURCH, DEP. CO. SURVEYOR
FD. 1/4 CORNER, NO WITNESSES NOTED | MARCH 5, 1964, MATT KOVISTO
SURVEY CHIEF, MSHD
SET 5/8" ROD PER FL CHURCH SURVEY
16" TWIN CEDAR N70°E 82.28'
POWER POLE S12°W 80.60'
FENCE POST NORTH 24.51'
JUNE 1971, MC FEINDT RLS
NOTED 1/4 CORNER, NO WITNESSES | NOV.7, 1978
NB DEYOUNG, RLS
FD. 3/4" PIPE
3/4" PIPE SOUTH 33.0'
3/4" PIPE N57°W 60.35'
JULY 19, 1997, JE FERGUSON
FD. 1/2" IRON,
FENCE POST S15°E 46.20' |
|--|---|---|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- L-13 DECEMBER 8, 1999
 FOUND 1/2" ROD NEAR NORTH EDGE OF GRAVEL ROAD
 16" CEDAR N70°E 82.28'
 POWER POLE S12°W 80.60' FOUND MICHIGAN STATE HIGHWAY DEPARTMENT TAG
 3/4" PIPE SOUTH 33.0'
 3/4" PIPE N57°W 60.33'
 C.L. GRAVEL ROAD SOUTH 9'
 FENCES TO NORTH AND SOUTH
 M-13 TO L-13 GLO 40 CHAINS (2640') MSHD 2604.76', MEASURES 2603.89'
 L-13 TO K-13 GLO 40 CHAINS (2640') MEASURES 2606.91'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-13 PLACED CHARLEVOIX COUNTY STEEL MARKER
 16" CEDAR N70°E 82.22' SET NAIL & TAG
 POWER POLE S12°W 80.60' SET NAIL & TAG
 3/4" PIPE SOUTH 33.0'
 3/4" PIPE N57°W 60.33'
 AND IS ACCEPTED AS A CAREFUL & FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER

Charlevoix Co. Surveyor
APPROVED
 Signature Mary C. Fennell
 Date: Dec 16, 1999

Signed by _____
 Surveyor's Michigan License No. 20703

Date _____



003 PAGE 298