

99 DEC 20 PM 2:12

Cherene M. Justice
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

T33NR9W (M-13) is the
 SAME CORNER AS T33N8W (A-13)

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Charlevoix (County)	Located In:	Corner Code #
1. Public Land Survey	T 33N R 8W	A-13
	T R	
	T 32N R 8W	A-1
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Wayne E. Boss

DECEMBER 99

I, _____, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-13 JUNE 5, 1839 JOHN HODGSON, DEPUTY SURVEYOR ESTABLISHED TOWN CORNER POST BEECH 16 INCH N53°W 11 LINKS BEECH 12 INCH N70°E 18 LINKS	MARCH 26, 1964 MATT A. KOVISTO, SURVEY CHIEF MICH.ST.HWY.DEPT. FD. BOTTOM OF OLD POST & STONE NEXT TO POST, PLACED 2"x3' AXLE SHAFT 9" ELM N85°W 72.46' 7" ELM NORTH 77.58'	FEB. 7, 1972 & JULY 31, 1987 MC FEINDT, RLS FOUND 2" AXLE SHAFT AT FENCE INTERSECTION SEP. 14, 1989, NB DEYOUNG, RLS FD. 2" AXLE SHAFT 6" MAPLE N. 67.00', 4" APPLE N20°W 7.20', 6" PINE S70°W 30.40' 6" PINE S15°W 21.30'
--	--	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-13 DECEMBER 8, 1999
 FOUND 2" AXLE SHAFT
 AT FENCE INTERSECTION
 12" MAPLE NORTH 67.00'
 4" APPLE N20°W 7.20'
 12" RED PINE S70°W 30.40'
 12" RED PINE S15°W 21.30'
 B-13 TO A-13 GLO 41 CHAINS (2706') MEASURES 2695.22'
 A-13 TO L-13 GLO 40 CHAINS (2640') MEASURES 2603.89'

Charlevoix Co. Surveyor
APPROVED
 Signature *Mary C. Feindt*
 Date: DEC 16 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-13 PLACED CHARLEVOIX COUNTY STEEL MARKER
 12" MAPLE N10°E 67.24' SET NAIL & TAG
 12" RED PINE S85°W 30.63' SET NAIL & TAG
 12" RED PINE S33°W 21.57' SET NAIL & TAG
 6" RED PINE S47°E 36.63' SET NAIL & TAG
 AND IS ACCEPTED AS A CAREFUL & FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER

Signed by *Wayne E. Boss*
 Surveyor's Michigan License No. 20703

Date _____
