

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --	LOCATED IN --	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. S., R. _____ E. W.	_____
2. PROPERTY CONTROLLING IN SECTION <u>26</u>	T. <u>33</u> N. S., R. <u>9</u> E. W.	<u>11</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. <u>33</u> N. S., R. <u>9</u> E. W.	<u>**666'-E OF COR CODE 10</u> <u>***674.3'-E OF I-11</u>
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, CARL ROSER, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on FEBRUARY 27, 1986, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on FEBRUARY 27, 1986, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 11 FD 3/8" IRON BY RLS, NICK DEYOUNG; SEE HIS 1978 CERT SUR OF NE 1/4 OF SW 1/4 OF S-26. OLD COR FN POST, DOWN, (B-W ON CED POST, E & S), IS 27'±N & 16'±E. SE COR OF NW 1/4 OF SW 1/4 OF S-26; REROD.
- * DROVE 5/8" X 34" REROD FOR NE COR OF W 1/2 OF SW 1/4 OF SW 1/4 OF SEC 26. A COR FN POST POSITION (COR POST DOWN IN PILE OF ROCKS-FN'S E & S) IS N62°28'E, 26.6'.
- ** DROVE 5/8" X 34" REROD FOR SE COR OF W 1/2 OF SW 1/4 OF SW 1/4 OF SEC 26. OLD N-S FN IS 7.5'-E. OLD E-W FN IS 26'-N. OLD FN COR (FN'S W & N) IS N44°54'E, 36.4'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

11	**	***
FD 3/8" X 18" N.B.D. IRON. REPLACED WITH 5/8" X 34" REROD W/RLS CAP & SET CED POST W/LOC TAG.	DROVE 5/8" X 34" REROD W/RLS CAP & SET CED POST W/LOC TAG.	DROVE 5/8" X 34" REROD W/RLS CAP & SET CED POST W/LOC TAG.
7" CEDAR S76°E 19.9	6" CED N30°E 67.2'	3" CED S30°W 9.4'
3" CEDAR S20°E 17.9	3" CED N56°E 43.8'	4" CED N18°W 11.9'
11" CEDAR N45°W 24.7	16" CED S10°E 128.9'	4" CED N08°E 32.5'


SIGNED BY Carl F. Roser 03-26-86 DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____



(SEAL)
CHARLEVOIX COUNTY
NORWOOD TOWNSHIP

SURVEYOR'S MICHIGAN REGISTRATION NO. _____