

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>33</u> N. <u>•</u> , R. <u>9</u> W. <u>•</u>	<u>K-5'</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____, R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION <u>14</u>	T. <u>33</u> N. <u>•</u> , R. <u>9</u> W. <u>•</u>	<u>**2452' W. OF K-5</u>
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, CARL F. ROSER, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on FEBRUARY 21, 1986, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on FEBRUARY 21, 1986, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- K-5 FD. ROUND CONC. MON. AS RECOVERED AND RECORDED ON OLD COUNTY "CORNER REGISTRY" ON 12-24-64. "EXIST. MON. PLACED BY NORTON-KOBINS IN SURVEY FOR "CLIPPER VIEW SUBDN."
 - ** FD. ROUND CONC. MON. FOR U.S.M.C. AS SET BY R.L.S. LARRY FEINDT AT RECORD U.S. (G.L.O.) DISTANCE (2451.74') WEST OF SE COR OF SEC. 11 & ON SOUTH LINE OF S-11 PER RECORDED PLAT OF "CLIPPER VIEW SUBDIVISION". SEE L. FEINDT CERT. OF SURVEY DATED AUG. 21, 1976.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-5	*
FD ROUND CONC. MON	FD. ROUND CONC. MON & SET CED. POST W/LOG TAG
** 16" W. BIRCH N76°W 49.4	** 8" W. BIRCH N75°E 38.15
5" W. BIRCH S80°E 71.9	** 7" CEDAR S65°W 9.66
** 10" W. BIRCH S32°E 56.5'	** 9" CEDAR S16°E 33.02
6" CEDAR S50°E 49.8	** SW. COR OF HOUSE N25°E 17.56
	FOUNDATION
** EQUALS 1964 WIT. TREE'S BY TED MILLER	** EQUALS OUR DATA ON L.F. WIT.'S, FACE NAILS.

SIGNED BY Carl F. Roser 03-26-86 DATE

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)
CHARLEVOIX COUNTY
NORWOOD TOWNSHIP

SURVEYOR'S MICHIGAN REGISTRATION NO. _____