

**SURVEY & REMONUMENTATION**

OCT 19 1998

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF CHARLEVOIX  
REGISTER

For corners in

Charlevoix

(County)

Located In:

Corner Code #

- |                                    |             |   |            |            |
|------------------------------------|-------------|---|------------|------------|
| 1. Public Land Survey              | <u>34</u> N | R | <u>8</u> W | <u>J-9</u> |
|                                    | T           | R |            |            |
|                                    | T           | R |            |            |
|                                    | T           | R |            |            |
| 2. Property Controlling in Section | S           | T | R          |            |
|                                    | S           | T | R          |            |
| 3. Miscellaneous Property in Sec.  | S           | T | R          |            |
|                                    | S           | T | R          |            |

98 SEP -8 PH 2: 15

*Mary C. Feindt*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Wayne E. Boss in a field survey on JULY 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9										●			
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- |     |  |  |
|-----|--|--|
| J-9 | OCTOBER 22, 1841                         | SEP. 3, 1897, D.C. NETTLETON, DEP. CO. SURVEYOR      |
|     | W. CATHCART, DEPUTY SURVEYER             | RESET CORNER USING REFERENCE TO OLD BEARING TREE     |
|     | SET WOODEN POST                          | MAPLE 7 INCH N53*W 121 LINKS                         |
|     | HEMLOCK 8 INCH N01*W 6 LINKS             | NOVEMBER 1965, MARY C. FEINDT, P.S. SHOWS IRON STAKE |
|     | HEMLOCK 4 INCH S10*W 8 LINKS             | NO WITNESS NOTED.                                    |
|     | 1894, J.S. DIXON DESIGNATES CORNER       | CORNER USED BY OTHER SURVEYERS ON SHEET 2            |
|     | IN UNRECORDED PLAT OF FOX & EATON'S ADD. |  |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- J-9 FEB. 1998  
FOUND 1/2 INCH ROD  
12" PINE S70\*W 4.30'  
11" PINE N30\*E 5.45'  
POWER POLE N05\*W 23.60'

Charlevoix Co. Surveyor  
**APPROVED**  
Signature Mary C. Feindt  
Date: Aug. 13, 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- J-9 PLACED 4" PVC AROUND 1/2" IRON AND FILED WITH CONCRETE  
13" PINE S70\*W 4.30' 3920 CAP & NAIL IN NE FACE  
11" PINE N30\*E 5.45' 3920 CAP IN SW FACE  
UTILITY POLE N05\*W 22.61 SET NAIL & TAG IN WEST FACE  
CHAIN LINK ANCHOR POST N01\*W 11.8'  
EASTERLY EXTENSION ON U.S. HIGHWAY 31 SOUTH 2.5'  
FROM AUXILIARY MEANDER CORNER TO J-9 S889\*56'04" E 1868.48'  
J-9 TO NEW SECTION CORNER AT K-9 S89\*56'04" E 2578.15'

AND IS ACCEPTED AS A CAREFUL & FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER



Signed by Wayne E. Boss  
Surveyor's Michigan License No. 20703

Date Aug. 24, 1998

SURVEY &  
REMONUMENTATION

OCT 19 1998

SECTION

Charlevoix

34N 8W J-9


J-9 CONTIUNED

APRIL 14, 1978, LAWRENCE R. FEINDT, P.S. RECORDED LAND RECORDATION CERTIFICATE WITH FOLOWING  
FOUND 1/2" ROD  
12" PINE S70\*W 4.30'  
11" PINE N30\*E 5.45'  
POWER POLE N05\*W 23.60'

OCTOBET 30, 1980 JOHN E. FERGUSON  
FOUND 1/2" ROD  
12" PINE S70\*W 4.3'  
11" PINE N30\*E 5.45'  
POWER POLE N58W 23.60'

APRIL 24, 1987, GEORGE J. AVENDT, P.S.  
FOUND 1/2" ROD  
12" PINE S70\*W 4.3'  
11" PINE N30\*E 5.45'  
POWER POLE N05\*W 23.60'

APRIL 25, 1991, GEORGE J. AVENDT, P.S.  
FOUND 1/2" ROD  
12' PINE S70\*W 4.3'  
11" PINE N30\*E 5.45'  
UTILITY POLE N05\*W 23.60'



*Wayne E. Boos*