

OCT 19 1998

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX
RECEIVED FOR RECORD

98 SEP 15 AM 10:05

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Charlotte W. Chamberlain
REGISTER OF DEEDS

For corners in

Charlevoix (County)	Located In:	Corner Code #
1. Public Land Survey	34N R 8W	J-10
	T R	
	T R	
	T R	
2. Property Controlling In Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Wayne E. Boss
I, _____, in a field survey on JULY 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

J-10 CORNER NOT SET BY GOVERNMENT LAND OFFICE SEPTEMBER 5, 1902, E.A. ROBINSON SHOWS CENTER POST AS BEING 183.43' EAST OF THE EXTENSION OF THE EAST LINE OF STOCKMAN'S ADDITION TO THE VILLAGE OF CHARLEVOIX

JANUARY 24, 1986, LAWRENCE R. FEINDT, P.S. PLACED T-IRON, SERVICE POLE N37*W 51.63' POWER POLE S25*W 62.06', SW COR GARAGE N10*W 36.61' SE COR PORCH HOUSE #407 S61*E 31.15'

JULY 13, 1987, GEORGE J. AVENDT, P.S. SHERMAN A. CHAMBERLAIN, P.S. FOUND T-IRON, NO WITNESS NOTED


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-10 FEB. 18, 1998
FOUND T-IRON & CAP IN CONCRETE WALK
SERVICE POLE N37*W 51.63' FOUND NAIL & CAP 21566
POWER POLE S25*W 62.06' FD. NAIL & CAP 21566
NW CORNER OF GARAGE N10*W 36.61'
SW COR CORNER OF PORCH HOUSE #407 S61*E 31.14'

Charlevoix Co. Surveyor
APPROVED
Signature *Mary C. Feindt*
Date: *Aug. 13, 1998*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-10 PLACED STEEL CHARLEVOIX MARKER IN CONCRETE WALK
SERVICE POLE N37*W
POWER POLE S25*W 62.06' USED NAIL & CAP SE FACE
NW CORNER OF GARAGE N05*W 36.61'
SW COR OF PORCH HOUSE # 407 S61*E 31.15'
NEW SERVICE POLE N30*W 42.88' SET NAIL & TAG EAST FACE
THIS POSITION NOT ESTABLISHED BY ORIGINAL GOV'T. SURVEYORS, THIS MONUMENT IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER



Signed by *Wayne E. Boss*
Surveyor's Michigan License No. 20703

Date *Aug. 13, 1998*