

REMONUM

NOV 21 1997

COMMISSION

For corners in

CHARLEVOIX (County)

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX
RECEIVED FOR RECORD

97 OCT 22 PM 3:09

REGISTER OF DEEDS

Form with fields for Public Land Survey, Property Controlling, Miscellaneous, Lot No., and Private Claims.

Register of Deeds Stamp & File Number

I, James E. Evans, in a field survey on Aug 11, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior...

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
D-3 Quarter corner common to Sections 5 and 8 T38N - R10W
GLO: Set Quarter post 5-25-31 EA Robinson
Beech 8" S56°W 17 lks. (11.22') Set 3/4" pipe in pit filled with stones
Beech 6" N18°E 30 lks (19.80') 12" Sugar S84°E 99lks (65.34')

6-21-79 Nicholas B. DeYoung PS #20705
LCRC Liber 2 Page 114
Found 4" curved iron bar raised with 1/2" rod
30" Maple S07°E 22.00'
26" Maple N10°E 39.20'
36" W. Birch S80°E 51.20'

9-4-84 John ferguson PS # 24595
Found both Robinson & DeYoung corners
Same witness as DeYoung to DeYoung corner
New witness to Robinson corner
20" Maple S85°E 65.72' 18" Maple N62°E 90.80' 7" Maple S70°W 24.83' 7" Birch N20°W 97.80'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
D-3 Quarter corner common to Sections 5 and 8 T38N - R10W

FOUND 3/4" PIPE SURROUNDED BY ROCKS AS ESTABLISHED BY ROBINSON 12FT SOUTH OF SOUTH EDGE OF GRAVEL ROAD.

Also found DeYoung rebar in center line of road.
GLO to E-3 = 2640' Gourdie, Fraser = 2706.00 Ferguson = 2705.02' DeYoung = 2644.98' Meas = 2704.66'
GLO to C-3 = 2640' Robinson = 2699.40 Ferguson = 2705.15' DeYoung = 2644.61' Meas = 2704.97'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
D-3 Quarter corner common to Sections 5 and 8 T38N - R10W


DUE TO USE OF THE ROBINSON CORNER BY MOST LOCAL SURVEYORS IT WAS DECIDED TO HONOR THE ROBINSON LOCATION AS THE BEST EVIDENCE OF THE ORIGINAL CORNER.
REPLACED ROBINSON PIPE WITH CHARLEVOIX COUNTY MONUMENT

20" MAPLE S85°E 65.72' SET NAIL & CAP #22431 IN NORTH SIDE (R=65.34')
18" MAPLE N62°E 90.80' SET NAIL & CAP #22431 IN NW SIDE (R=90.80')
6" MAPLE NORTH 43.42' SET NAIL & CAP #22431 IN EAST SIDE
10" MAPLE S80°W 24.55' SET NAIL & CAP #22431 IN NORTH SIDE (R=24.83')
1/2" ROD USED BY DEYOUNG N76°E 61.77'

Charlevoix Co. Surveyor
APPROVED
Signature Mary C. Feurich
Date: Oct 9 1997

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by [Signature]



Date 10-21-97

Surveyor's Michigan License No. 22431

LIBER 003 PAGE 114