

SAME AS P. 5 17. 2000

STATE OF MICHIGAN
COUNTY OF CHARLEVOIX
REGISTERED PUBLIC RECORD

99 DEC 17 AM 9:45

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Chlorine M. Justice

For corners in

CHARLEVOIX
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 38N R 10W I-1
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

REGISTER OF DEEDS

RECORDED

FEB 13 2000

SECTION

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, James E. Evans, in a field survey on Oct. 29, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 I-1 SECTION CORNER COMMON TO SECTIONS 34 & 35 T39N - R10W and 2 & 3 38N - R10W
 GLO: Set post
 BEECH 9° N24°W 20 lks. (13.20') SUGAR 12° N19°E 16 lks (10.56')
 Y. BIRCH 14° S62°E 10 lks (6.60') BEECH 12° S28°W 16 lks (10.56')
 Sept 1845 By John Burt DS

- 6-17-76 - Wayne E. Boss PS #20703 Found 3/4" pipe 6" Birch N85°E 13.82' 6" Maple S35°W 18.28' 4" Maple N85°W 11.09'
- 7-11-78 - Lawrence R. Feindt PS #21566 Found 3/4" pipe used in survey for Rodney McFarland Same witnesses as W. Boss
- 7-16-87 - Mary C. Feindt PS #3920 Found 3/4" pipe and used in survey for Carl Evans Same witnesses as w. Boss.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 I-1 SECTION CORNER COMMON TO SECTIONS 34 & 35 T39N - R10W and 2 & 3 38N - R10W

Charlevoix Co. Surveyor
APPROVED
 Signature Mary C. Feindt
 Date: Dec 16, 1999

FOUND 3/4" PIPE IN CENTER LINE OF TWO TRACK ROAD

I-1 to I-12 (T39N-R10W) GLO = 2640' L. R. Feindt = 2645.38' S. A. Chamberlain = 2645.34' W. E. Boss = 2645.42'
 Meas = 2645.45'
 I-1 to H-13 (T39N-R10W) GLO = 2640' S. A. Chamberlain = 2666.91' Meas = 2667.01'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 I-1 SECTION CORNER COMMON TO SECTIONS 34 & 35 T39N - R10W and 2 & 3 38N - R10W

FOUND 3/4" PIPE IN CENTER LINE OF TWO TRACK ROAD ON LINE WITH FENCE TO THE EAST
 REPLACED PIPE WITH CHARLEVOIX COUNTY MONUMENT

- 3" APPLE N20°E 36.14' SET NAIL & CAP #22431 IN NW SIDE
- 8" BIRCH N85°E 13.82' FOUND PK NAIL IN SOUTH SIDE (R = 13.82')
- 8" MAPLE S35°W 18.32' FOUND NAIL IN EAST SIDE (R = 13.28')
- 6" MAPLE N85°W 11.05' FOUND NAIL IN NORTH SIDE (R = 11.09')

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by James E. Evans
 Surveyor's Michigan License No. 22431

Date 12-16-99

