

STATE OF MICHIGAN  
 COUNTY OF CHARLEVOIX  
 RECEIVED FOR RECORD

99 DEC 17 AM 9:40

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

CHARLEVOIX  
 (County)

Located In: Corner Code #

- 1. Public Land Survey T 39N R 10W G-9  
 T R  
 T R  
 T R
- 2. Property Controlling S T R  
 in Section S T R
- 3. Miscellaneous S T R  
 Property in Sec. S T R
- 4. Lot No. , Recorded Plat
- 5. Private Claims

*Charles B. Justice*  
 REGISTER OF DEEDS

FEB 17 2000

SECTION  
 Register of Deeds Stamp & File Number

I, James E. Evans, in a field survey on Oct. 29, 1999  
 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points  
 mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as  
 required in the current manual of survey instructions of the United States Department of the Interior,  
 Bureau of Land Management or by a decree of a Court of Law and /or that the corner points  
 mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of  
 Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented,  
 recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded  
 on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 G-9 Section corner common to Sections 21, 22, 27 and 28 T39N - R10W

GLO: Set post 10-05-49 Mary C. Feindt PS #3920  
 Beech 9" S38°W 27 lks. (17.82') Set iron 1320' West of existing iron  
 Maple 16" N36°E 42 lks (27.72') No witnesses  
 Sept 1845 By John Burt DS

2-2-89 George J. Avendt Jr. PS # 16034  
 Found Charlevoix Co. Monument  
 8" Wt. Pine N70°W 45.40'  
 5" Birch S60°W 58.05'  
 5" Wt. Pine S60°W 58.83'

12-13-85 Lawrence R. Feindt PS #21566  
 Found 3/4" pipe replaced with Chx Co. Monument  
 8" Wt. Pine N70°W 45.40'  
 5" Birch S60°W 58.05'  
 5" Wt. Pine S60°E 53.83'

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 G-9 Section corner common to Sections 21, 22, 27 and 28 T39N - R10W

FOUND CHARLEVOIX COUNTY ALUMINUM MONUMENT

GLO to H-9 = 2640' Mary Feindt = 2639.0 George Avendt = 2638.95' Meas = 2639.03'

Charlevoix Co. Surveyor  
**APPROVED**  
 Signature Mary C. Feindt  
 Date: Dec. 16, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 G-9 Section corner common to Sections 21, 22, 27 and 28 T39N - R10W

FOUND CHARLEVOIX COUNTY ALUMINUM MONUMENT.  
 APPROX. 40 FEET SOUTH OF SOUTH EDGE OF DONEGAL BAY ROAD.

12" WHITE PINE N82°E 45.44' FOUND CAP #21566 IN NORTH SIDE (R=45.40)  
 8" OAK S50°W 12.74' SET NAIL & CAP #22431 IN NORTH SIDE  
 5" OAK N67°W 44.33' SET NAIL & CAP #22431 IN NE SIDE  
 8" WHITE PINE N01°W 110.06' SET NAIL & CAP #22431 IN SW SIDE

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by *James E. Evans*  
 Surveyor's Michigan License No. 22431

Date 12-16-99

