

99 DEC 17 AM 9:42

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Chalene W. Neustrom

REGISTER OF DEEDS

For corners in

CHARLEVOIX
 (County)

Located In:

Corner Code #

- | | | | |
|------------------------------------|---------|---------------------------|-------------|
| 1. Public Land Survey | | T <u>39N</u> R <u>10W</u> | <u>H-11</u> |
| | | T _____ R _____ | _____ |
| | | T _____ R _____ | _____ |
| | | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ | T _____ R _____ | _____ |
| | S _____ | T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ | T _____ R _____ | _____ |
| | S _____ | T _____ R _____ | _____ |

RF
 FEB 10 2000
 SECTION

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, James E. Evans, in a field survey on Oct. 29, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-11 QUARTER CORNER COMMON TO SECTIONS 27 and 34 T39N - R10W
 GLO: Set post SPRUCE 6" S50°E 17 lks. (11.22')
 TAMARACK 3" N67 1/2°E 20 lks (13.20')
 Sept 1845 By John Burt DS

8-29-74 - Lawrence R. Feindt PS #21566 Found 5/8" rod West end culvert N80°W 27.21' East end culvert N75°E 33.23'
 8" Tamarack N35°W 80.35'

- 9-01-78 - L. R. Feindt used same corner for survey for Francis Ricksgers. Same witnesses.
- 3-07-79 - Sherman A. Chamberlain Jr. PS #25834 filed LCRC Liber 2 Page 97 Same witnesses.
- 6-22-79 - John E. Ferguson PS #24595 recorded survey Liber 352 Page 772 Refers to 9/16" rod Same witnesses.
- 6-24-81 - John E. Ferguson used 9/16" rod for survey for Edward Palmer Same witnesses.
- 8-05-81 - Sherman A. Chamberlain Jr used 1/2" rod for survey for Carol O'Donnell Same witnesses.
- 6-12-86 - L. R. Feindt Found 5/8" rod and used for survey for Harry Gill Same witnesses.

Charlevoix Co. Surveyor
APPROVED
 Signature *Mary C. Feindt*
 Date: Dec 16 1999

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 H-11 QUARTER CORNER COMMON TO SECTIONS 27 and 34 T39N - R10W

FOUND REBAR & CAP # 25834 (Sherman A. Chamberlain) IN MONUMENT BOX IN CENTER LINE OF KING'S HIGHWAY.

H-11 to I-11 GLO = 2640' L. R. Feindt = 2640.10' J. E. Ferguson = 2639.60 Meas = 2639.54'
 H-11 to H-12 L. R. Feindt = 2648.05' S. A. Chamberlain = 2648.06' J. E. Ferguson = 2648.08' Meas = 2648.46'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 H-11 QUARTER CORNER COMMON TO SECTIONS 27 and 34 T39N - R10W

FOUND REBAR & CAP # 25834 (Sherman A. Chamberlain) IN MONUMENT BOX IN CENTER LINE OF KING'S HIGHWAY

- 24" CULVERT N86°E 34.38' SET NOTCH IN EAST END (R=33.23')
- 5" BIRCH S65°E 76.89' SET NAIL & CAP #22431 IN NORTH SIDE
- 6" ELM S60°W 41.440' SET NAIL & CAP #22431 IN NW SIDE
- 24" CULVERT N70°W 27.45' SET NOTCH IN WEST END (R=27.21')

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by *James E. Evans*

Date 12/16/99

Surveyor's Michigan License No. 22431

