

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 33 N.R. 1 E


Cheboygan COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 4-5

CORNER MONUMENT Set 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 10/31/62

WITNESSES TO CORNER.....



6" Cedar - N4W - 7.5 ft

6" Cedar - S8W - 19.7 ft

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set by proportionate measurement between section corners while making a survey in this area. Unable to locate a previous corner or any US evidence. Checks very well with stream crossing north and swamp edge south. Falls off west edge of N-S fireline.

SURVEYOR'S SEAL

SIGNED *Kenneth H. Ostling* DATE 11/7/62
REGISTERED LAND SURVEYOR