

*Surveying*

CONS. 4047  
REV. 10/60

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 33 N.R. 1 E.  
T. 33 N.R. 1 W.


Cheboygan COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 13 - 24 - 18 - 19

CORNER MONUMENT Set 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED October 31, 1962

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

10" Cedar S 39 W 44.3'

10" Cedar N 59 W 44.6'

AND

12" Balsam N 37 E 9.9

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set while making a survey of the meridian. Could locate no previous corner. Set corner at intersection of N - S and W firelines. Check marsh edge east and appears to be the only practical location for corner. Okay for measurement north and south.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Osting* DATE November 26, 1962  
REGISTERED LAND SURVEYOR