

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Cheboygan</u> <small>(County)</small>	Located In:	Corner Code ##
1. Public Land Survey	T <u>33N</u> R <u>1E</u>	<u>L-1</u>
	T <u>33N</u> R <u>1E</u>	<u>M-2</u>
	T <u>33N</u> R <u>1E</u>	<u>K-2</u>
	T <u>33N</u> R <u>1E</u>	<u>K-1</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Carl R. Johnson, in a field survey on August 25, 19 87, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-1 - Set on township line midway between section corner.

M-2 - Set in centerline of road east and west and on line between found section corner south and section corner north computed to be established at GLO record distance east of SE corner of Sec. 36, T34N, R1E.

K-2 - Set in centerline of road east and on line between found section corner south and section corner north established at GLO record distance east of SW corner Sec. 36, T34NR1E

K-1 - Set at record distance east of SW corner Section 36, T34N, R1E, and on township line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-1 - N $\frac{1}{2}$ corner
3/4" x 36" pipe w/cap
 No witnesses available.

M-2 - E $\frac{1}{2}$ Cor
 DNR Monument
 10" Cedar S6 $^{\circ}$ E 97.0'
 10" Cedar S68 $^{\circ}$ W 80.4'
 Cedar post w/TAG N5 $^{\circ}$ E 25.0'
 Set in $\frac{1}{8}$ of E-W Road

K-2 - W $\frac{1}{2}$ Corner
 Set DNR Mon.
 Power Pole w/ref. marker N43 $^{\circ}$ E 48.77'
 Power Pole w/ref. mker. S36 $^{\circ}$ W 56.50'
 Cedar Post N4 $^{\circ}$ E 50.0'

K-1 - NW Corner
 DNR Mon.
 Fence Post w/ref. mkr. East 9.45'
 Fence Post w/ref. mkr. West 18.34'

Signed by Carl R. Johnson
 Surveyor's Michigan License No. 30083

Date 1/4/88

