

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>33</u> N. R. <u>1</u> W.	<u>C-3; C-2</u>
2. PROPERTY CONTROLLING IN SECTION <u>6</u>	T. <u>33</u> N. R. <u>1</u> W.	<u>14; 7</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, KENNETH J. OSTLING, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on DECEMBER 1, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

B. CONTINUED:
~~Deposited in public records and accessories and or subsequent restoration~~

7 - SET BY STANDARD SURVEY PROCEDURE FOR SUBDIVISION OF SECTIONS. FENCE IS ABOUT 75' WEST AND 7' SOUTH OF CORNER.

C. CONTINUED:

- 7
- SET 5/8" ROD W/RLS CAP
 - 6" CEDAR S12°W 16.1'
 - 8" CEDAR N70°E 18.0'
 - SQ.4" BALSAM S38°W 2.2'
 - CORNER FALL 8.0' NORTH OF E-W WIRE

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-3 - SET CORNER IN \odot EW COUNTY ROAD AT PROPORTIONATE MEASUREMENT BETWEEN THE S 1/4, SECTION 5 AND SW CORNER SECTION 6. BELIEVE THIS CONFORMS CLOSELY WITH SCHAAF SURVEY IN EARLY 1940'S.
- 14 - SET BY STANDARD SURVEY PROCEDURE FOR THE SUBDIVISION OF SECTIONS. FENCE IS ABOUT 23' WEST AND 12' SOUTH OF CORNER.
- C-2 - SET CORNER BY SINGLE PROPORTIONATE MEASUREMENT BETWEEN SECTION CORNERS. NO U.S. EVIDENCE. FOUND PIPE IN CONCRETE MONUMENT ON SURFACE OF GROUND AT FENCE LINE ABOUT 48' WEST OF CORNER. DO NOT BELIEVE IT WAS EVER PROPERLY LOCATED.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>C-3</u>	<u>14</u>	<u>C-2</u>
5/8" ROD W/RLS CAP	SET 5/8" ROD W/RLS CAP	SET D.N.R. MONUMENT
6" W. PINE N60°E 38.8'	8" W. PINE N66°E 6.8'	10" CEDAR S50°W 17.2'
12" W. PINE S9°E 34.4'	10" W. PINE N77 1/2°W 17.8'	12" CEDAR S40°E 20.2'
CORNER SET IN \odot OF ROAD E-W	FENCE CORNER S67°W 26.3'	

SIGNED BY Kenneth J. Ostling

DATE 2/6/84

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

CHEBOYGAN COUNTY