

**SURVEY & REMONUMENTATION**

MAY 05 1997

**COMMISSION**

**RE MONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED  
FOR RECORD

96 NOV 25 PM 12:48

*Janice Gray*  
CLERK/REGISTER  
CHEBOYGAN COUNTY, MICHIGAN

Cheboygan (County) Located In: Corner Code #

1. Public Land Survey T 33N R 3W M-4  
T     R      
T 33 R 02 A-04  
T     R    

2. Property Controlling in Section S     T     R      
S     T     R    

3. Miscellaneous Property in Sec. S     T     R      
S     T     R    

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Brian K. Fullford, in a field survey on August, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

- A. Description of original monument and accessories and/or subsequent restoration:
- |                           |                                  |                           |
|---------------------------|----------------------------------|---------------------------|
| G.L.O.                    | 1923 Recorded In County Surveyor | 1957 LCRC                 |
| Set 1/4 Corner            | Records Survey By David Bowen    | Liber A, Page 65          |
| 10" Spruce S01°W 31 Links | Cedar Post In Center of N/S Road | Orlando Doyle #7319       |
| 10" Cedar N51°W 25 Links  |                                  | Fnd Concrete Monument     |
|                           |                                  | 6" Cedar N51°30'E 22.32'  |
|                           |                                  | 12" Cedar S20°E 31.75'    |
|                           |                                  | 10" Cedar S61°30'W 53.00' |

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Fnd Broken Concrete Monument  
Fnd 12" Cedar N51°30'E 22.26' (Doyle Witness)

LIBER 010 PAGE 192




- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-4 Fnd Broken Concrete Monument. Replaced with 5/8" x 36" Bar & Remon Cap 4" Below Grade in Center Line of 2 Track. Accepted as a careful & faithful re-establishment of the position of the original corner.

- 12" Cedar N51°30'E 22.26 w/60p nail
- 10" Cedar S54°E 27.16' w/60p nail
- 15" Poplar S76°W 21.19' w/60p nail
- 18" Poplar N39°W 31.07' w/60p nail

*Maria A. Rice*



THIS CORNER IS ALSO DESIGNATED AS CORNER CODE #A-4, T33N-R2W.

Signed by Brian K. Fullford  
Surveyor's Michigan License No. 41099  
Brian K. Fullford, PS

Date 10/22/96