

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
CHEBOYGAN
 (County)

Located In: Corner Code #

1. Public Land Survey T 33N R 02W D-9, E-10
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, CARL T. KIISKILA, in a field survey on AUGUST 14, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
 D-9 E-10

(NO EVIDENCE OF G.L.O. CORNER, B.T'S, LINE TREES & TOPOGRAPHY, AS CALLED OUT IN THE G.L.O. LINE NOTES; UNLESS NOTED IN ITEM "B" BELOW.)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 D-9 E-10

FOUND AND ACCEPTED A 1 1/2" PIPE, RAISED WITH 1" BAR, AS WITNESSED IN 1959 BY A MSHD SURVEY CREW WHILE DOING A ROUTE SURVEY IN THE AREA. THIS CORNER WAS ALSO ACCEPTED BY JAMES SCHMANDT, P.S.#26466, WHILE DOING A SURVEY IN SECTION 29.

FOUND AND ACCEPTED A 1/2" IRON PIN IN THE CTR. OF OLD N-S ROAD BED. THIS PIN HAS BEEN ACCEPTED BY ADJACENT LAND OWNERS AND PREVIOUS SURVEYORS AS BEING THE TRUE POSITION OF THE ORIGINAL CORNER. THIS CORNER ALSO FITS WELL WITH THE ACCEPTED CTR. OF SECTION 29, 1/2 MILE TO WEST.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-9	E-10
FOUND 1" IRON ROD IN CTR. E-W GRAVEL ROAD.	FD 1/2" IRON PIPE IN CTR OLD ROAD BED, DROVE 1" X 32" I.P. OVER 1/2" I.P.
4" SQUARE POST SOUTH 31.69'	W. PINE 8" N17°W 58.57'
FM COR POST N03°W 34.38'	TAMARACK 6" S54°W 47.01'
#ELM 6" N71°E 59.95'	W. PINE 3" S63°E 52.12'
#ELM 3" DEAD N21°W 34.37'	DBL.CEDAR 4" N57°E 72.22'
#ELM 4" DEAD S69°W 61.75'	STEEL FN. POST NORTH 1.0'



* = OLD MIT. BY OTHERS.

Signed by Carl T. Kiiskila Date 3-28-97

Surveyor's Michigan License No. 33981