

MAY 05 1996

COMMISSION

For corners in

Cheboygan

(County)

1. Public Land Survey

Located In:

Corner Code #

T	34N	R	1W	M-6
T		R		
T	34	R	1E	A-6
T		R		
S		T	R	
S		T	R	
S		T	R	
S		T	R	

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

RECEIVED FOR RECORD

96 NOV 25 PM 1:06

J. J. Gray
CLERK/REGISTER
CHEBOYGAN COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

I, Brian K. Fullford, in a field survey on August, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.	1966 D.O.C. Corner Record
Set 1/4 Section Post	Kenneth Ostling #10068
7" Beech S22°W 17 Links	Set 1" Pipe w/4" Brass Cap
8" Maple N41°E 19 Links	Set Proportionate Measurement
	9" Red Oak N45°W 20.7'
	8" Red Oak N56°E 13.6'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fnd 1" Pipe with Department of Conservation 4" Brass Cap
12" Red Oak N49°W 20.51' (Ostling Witness)
12" Red Oak N56°E 13.98' (Ostling Witness)



LIBER 010 PAGE 208

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6 Fnd 1" Pipe with Department of Conservation 4" Brass Cap. Accepted as a careful & faithful re-establishment of the position of the original corner.

12" Red Oak N56°E 13.98' Set Tag
4" Maple S11°W 10.30' Set Tag
5" Red Oak S70°W 20.81' Set Tag
12" Red Oak N49°W 20.51' Set Tag

THIS CORNER IS ALSO DESIGNATED AS CORNER CODE #A-6, IN T34N-R1E.

Signed by Brian K. Fullford 44099

Surveyor's Michigan License No. _____

Brian K. Fullford, PS

Date 10/22/96

