

SURVEY & REMONUMENTATION

MAY 05 1997

**RE MONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECEIVED FOR RECORD

96 NOV 25 PM 1:09

James Gray
CLERK/REGISTER
CHEBOYGAN COUNTY, MICHIGAN

COMMISSION

For corners in

<u>Cheboygan</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>34</u> N R <u>1</u> W	M-8
	T <u> </u> R <u> </u>	
	T <u>34</u> R <u>1E</u>	<u>A-08</u>
	T <u> </u> R <u> </u>	
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	
	S <u> </u> T <u> </u> R <u> </u>	
3. Miscellaneous	S <u> </u> T <u> </u> R <u> </u>	
Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Brian K. Fullford, in a field survey on August, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	19	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
G.L.O. 1951 LCRC
Set 1/4 Section Post Liber A, Page 114
7" Hemlock S87°W 6 Links Set 1" Pipe with Dept of Conservation 4" Brass Cap
11" Cedar N54°E 8 Links By Proportionate Measure
Dean DeLamater #5778
8" White Birch S87°W 5 Links
8" Cedar N87°E 109 Links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Fnd 1" Pipe W/Dept. Of Conservation 4" Brass Cap
White Birch Stump S87°W 3.0' (DeLamater Witness)
14" Cedar N87°E 72.10' (DeLamater Witness)



LIBER 010 PAGE 210

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-8 Fnd 1" Pipe w/Dept. Of Conservation 4" Brass Cap. Accepted as a careful & faithful re-establishment of the position of the original corner.
5" Balsam N24°E 3.48' Set Tag
14" Cedar N87°E 72.10' Set Tag
6" Balsam S04°W 17.88' Set Tag
4" Balsam S53°W 7.60' Set Tag

THIS CORNER IS ALSO DESIGNATED AS CORNER CODE #A-8, IN T34N-R1E.

Signed by *Brian K. Fullford*
Surveyor's Michigan License No. 41099
Brian K. Fullford, PS

Date 10/22/96

