

1998

1998 CHEBOYGAN COUNTY, STATE OF MICHIGAN REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Cheboygan Located In: Corner Code #
Forest Township
1. Public Land Survey T34N R 1E F-3
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

RECEIVED FOR RECORD 12-7-98
at 9:38 O'Clock A.M

Signature of Joanne Spraf

CLERK/REGISTER
CHEBOYGAN COUNTY, MICHIGAN
Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

I, Ronald Bischer, in a field survey on 7-17, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-L and rows 1-13. A dot is marked at the intersection of column F and row 3.


A. Description of original monument and accessories and/or subsequent restoration:

F-3
1855 George Cannon (Resurvey)
Set wood post
N19°W 31 lks 7" W. pine
S1 1/2°E 37 lks 7" Y. Pine
April 2, 1960 Dean DelaMater #2674
Chisled cross in blacktop
2 witnesses

Jan 24, 1975 Delmer Porter #15410
Set p.k. nail by S.P.
3 witnesses
July 29, 1981 Delmer Porter #15410
3/4" Rod and 3 witnesses
Sept 23, 1983 Delmer Porter #15410
found 3/4" ROD and 3 witnesses
Dec 13, 1988 Clifford Lindgren #1409
found P.K. reste with 1/2" rod and cap
5 witnesses left


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-3
Found 1/2" rod and cap #14098 in mon box
placed remon cap on 1/2" rod in mon box



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-3
1/2" rod and remon cap in mon box
S10°E 48.57' P. Pole
S10°W 31.02' 3/4" rod O.W.
S08°W 57.10' North face of R/W marker O.W.
N38°E 88.00' 30" Maple O.W.



LIBER 011 PAGE 103

Signed by Ronald R. Bischer
Surveyor's Michigan License No. 22428

Date Sept. 28, 1998