

1999 CHEBOYGAN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Cheboygan</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>34</u> N R <u>1E</u>	<u>G-4</u>
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Ronald Bischer, in a field survey on Aug. 12, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

G-4	Jan 17, 1975 Delmer Porter #15410 cons. marker
1855 GLO Notes Resurvey	East 71.70' 5" J. Pine
S62 $\frac{1}{2}$ °E 12 lks 10" Hemlock	S02° E 72.71' 9" R. Pine
N79°W 14 lks 10" Hemlock	N58° W 39.62' 6" Birch
April 2, 1960 CCLC by Dean DelaMater#2674	June 25, 1995 Norman Quaine#33984 cons marker
1" Pipe with 4" brass cap	N18°W 65.40' 9" Balsam
N67°W 39.5' 7" W. Birch	N78° E 53.47' 7" J. Pine
S03°E 72.7' 2" R. Pine	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-4	S61° E 86.72' 12" R. Pine
Aug. 12, 1999 Cheboygan County Remonumentation	S04° W 72.68' 13" R. Pine
Ronald Bischer #22428	
found cons marker bent over replace with 5/8" rod and cap	
found 4 witnesses	

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-4
5/8" rod and cap #22428
N18°W 65.20' 7" Balsam
N78°E 53.46' 7" J. Pine
S05°W 76.68' 13" Norway
S61°E 86.78' 12" Norway

007 7 999
James H. Shanger



LIGER 011 PAGE 168

Signed by Ronald R. Bischer
Surveyor's Michigan License No. 22428

Date 12-18-99