

1999 CHEBOYGAN COUNTY REMONUMENTATION

RECEIVED  
FOR RECORD

99 DEC 27 PM 4: 12

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Cheboygan  
(County)

Located In: Corner Code #

1. Public Land Survey	T 34N R 1E	I-4
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

*Deby Pizzomati*  
CLERK/REGISTER  
CHEBOYGAN COUNTY MICHIGAN

MAR 03 2000

SECTION

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Ronald Bischer, in a field survey on Aug. 12, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- I-4
- 1855 GLO Notes Resurvey
- S30°E 8 lks 6" Y. Pine
- N33°E 22 lks 6" Y. Pine
- Dec. 7, 1977 Ronald Bischer #22428 found 3/4" Bar
- N24°E 18.89' 5" Oak
- S85°E 76.25' Well point
- S50°E 10.50' 4" Norway

June 17, 1996 Thomas Hall #41100  
3/4" bar  
Same witnesses as above  
Jan 16, 1997 Norman Quaine #33984  
Same as above

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- I-4
- Aug. 12, 1999 Cheboygan County Remonumentation
- Ronald Bischer #22428
- found 3/4" bar replaced with 5/8" Rod and cap #22428
- found all 4 witnesses



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-4
- 5/8" bar and cap #22428
- S48°E 10.53' 9" R. Pine
- N27°E 18.81' 6" Maple
- S82°W 6.08' 9" Red pine
- S84°E 76.28' Well Point
- N45°E 50' centerline of Two-track

LIBER 011 PAGE 169



Signed by Ronald R. Bischer  
Surveyor's Michigan License No. 22428

Date 12-18-99