

1999 CHEBOYGAN COUNTY REMONUMENTATION

RECEIVED
FOR RECORD

99DEC 27 PH 4: 16

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

CHEBOYGAN
(County)

Located In:

Corner Code #

1. Public Land Survey

T 34 N R 1 E L-5

T R

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Debra Pyszynski
CLERK/REGISTER
CHEBOYGAN COUNTY MICHIGAN

MAR 03 2000

SECTION
Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	I
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Ronald Bischer, in a field survey on Aug. 10 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-5

1855 GLO Notes Resurvey
S07° E 36½ lks 9" W. Pine
N17° W 23½ lks 8" W. Birch

May 29, 1974 Delmer Porter #15410
3/4" Bar in N/S fence line
and old R x R grade
North 24.15' South gate post
South 10.92' fence post

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-5

Aug. 10, 1999 Cheboygan County Remonumentation
Ronald Bischer #22428
found 3/4" bar replaced with 5/8" Bar and cap #22428
found both old witnesses
set 2 new witnesses



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-5

5/8" bar and cap #22428
North 23.68' South gate post
S52° E 1.30' fence post
South 14.85' fence post
North 11.94' fence post

LIBER 011 PAGE 172



Signed by Ronald R. Bischer
Surveyor's Michigan License No. 22428

Date 12-18-99