

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 34 N. R. 1 E


Cheboygan COUNTY

DESCRIPTION OF CORNER Section corner common to sections 16, 17, 20 and 21

CORNER MONUMENT Drove 1/2 x 1 1/4" iron bar below surface of road

DATE MONUMENT PLACED AND WITNESSED December 14, 1965

WITNESSES TO CORNER.....



1 1/4" H. Maple S50E 66.9

Corner Fence post S37W 34.2

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored at the apparent centerline inter-section of county roads E-W-N-S. Unable to locate anything for corner after extensive search. All existing corners in area appear to conform with road alignments which indicates the roads were constructed according to a survey and are in fact a monument to the section lines. No other evidence available.

SURVEYOR'S SEAL

SIGNED

Kenneth J. Osting
REGISTERED LAND SURVEYOR

DATE

December 30, 1965

X