

✓

**MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION**

LAND CORNER RECORD

T. 34 N.R. 1 E


Cheboygan COUNTY

DESCRIPTION OF CORNER Section corner common to sections 21, 22, 27, and 28

CORNER MONUMENT Drove 5/8" x 16" iron bar below road surface

DATE MONUMENT PLACED AND WITNESSED December 13, 1965

WITNESSES TO CORNER.....



Beech clump N64 E 48.8

5" Maple S44 E 64.6

AND Power Pole S66 W 29.7

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set on line between section corners 1 mile north and south, at a measurement most in conformance with fence lines of occupation in both sections. Could find no evidence of previous corner. Falls in line with trail roads east and west.

SURVEYOR'S SEAL

SIGNED Kenneth J. Ostling DATE December 30, 1965
REGISTERED LAND SURVEYOR #10068