

✓

**MICHIGAN**  
**DEPARTMENT OF CONSERVATION**  
**FORESTRY DIVISION**

# LAND CORNER RECORD

T. 34 N.R. 1 E


Cheboygan COUNTY

**DESCRIPTION OF CORNER** Section corner common to sections 20, 21, 28, and 29

**CORNER MONUMENT** Set 1" pipe with 1/4" aluminum cap

**DATE MONUMENT PLACED AND WITNESSED** December 13, 1965

**WITNESSES TO CORNER.....** \_\_\_\_\_



16" Red Pine      N 48 E      30.8

10" Red Pine      N 76 W      63.2

**AND** \_\_\_\_\_

CIRCLE CORNER REGISTERED

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

This corner was set by single proportionate measurement between Section corner north and 1/4 corner south. Original survey constructed this as straight line so corner was restored on same basis. Fits pattern of survey for both sections.

**SURVEYOR'S SEAL**

SIGNED *Kenneth J. Osting* DATE December 30, 1965  
REGISTERED LAND SURVEYOR # 19068