

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 34 N.R. 1 E


Cheboygan COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 20-29

CORNER MONUMENT Set 1" pipe with 1/2" aluminum cap

DATE MONUMENT PLACED AND WITNESSED April 26, 1966

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

7" J. Pine S 81 E 7.7'

7" J. Pine N 2 W 50.4'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set by proportionate measurement  
between section corners. Nothing definite for U. S. evidence.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Ostling* DATE April 28, 1966  
REGISTERED LAND SURVEYOR #10068