

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T 34 NR 1 E

Cheboygan

COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 9 and 10

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

7" W. Birch - N67W - 39.5 feet
2" R. Pine - S3E - 72.7 feet

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division survey crew while making a survey of Section 9. Set corner midpoint, on line between section corners. All government evidence gone, and no evidence of previous corner. This point falls about 3' south of fence lines east and west, and about 5' west of a fence that starts near here and runs southerly on a somewhat meandering course.

Corner was placed and witnessed November 11, 1959.

SURVEYORS SEAL

SIGNED *Kenneth J. Oetting*
REGISTERED LAND SURVEYOR

DATE 11/16/59