

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 34 NR. 1E

Cheboygan COUNTY

DESCRIPTION OF CORNER 1/4 corner at center of Section 9

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

6" Maple	-	S65W	-	5.4 feet
7" Maple	-	S40E	-	7.5 feet

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established on the true E-W 1/4 line at its calculated intersection with the N-S 1/4 line by Forestry Division land surveyor while making a survey of Section 9. Corner falls 1' west of a well constructed N-S fence through Section 9. Could find no evidence of previous corner.

Corner was placed and witnessed November 11, 1959.

SURVEYORS SEAL

SIGNED Kenneth J. Bethune DATE 11/16/59  
REGISTERED LAND SURVEYOR