

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 34 NR. 1 E

Cheboygan

COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 9-10-15-16

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

7" R. Oak	-	S80W	-	24.7 feet
8" Beech	-	S58E	-	16.6 feet

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division surveyor while making a survey of Section 9. Set corner by double proportionate measurement between corners 1 mile north, 1 mile south, 1 mile west, and  $\frac{1}{2}$  mile east. This point falls at intersection of old township road grades east and south. A large excavation at this point has removed any evidence of a previous corner or witnesses. This restoration appeared to satisfy all adjoining equities, and was considered justified in the absence of evidence of a previous corner. This point fits the centerline of old roads east and south, and conforms to traces of an old fence line on the south line of Section 9.

Corner was placed and witnessed November 11, 1959.

SURVEYORS SEAL

SIGNED

*Kenneth J. Oetting*  
REGISTERED LAND SURVEYOR

DATE 11/16/59