

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 34. NR. 1 E.

Cheboygan

COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 9 and 16

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

|           |   |      |   |           |
|-----------|---|------|---|-----------|
| 9" Beech  | - | N60E | - | 17.5 feet |
| 10" Beech | - | S36E | - | 16.0 feet |

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement between section corners- midpoint, on line- by Forestry Division land surveyor while making a survey of Section 9. Could make no positive identification of government BTs, and could find no previous corner. Corner falls about 5' west of apparent fence line from the north which ends some 200' north of the corner.

Corner was placed and witnessed November 11, 1959.

SURVEYORS SEAL

SIGNED Kenneth J. Ostling DATE 11/16/59  
REGISTERED LAND SURVEYOR