

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 34 N.R. 1 E


Cheboygan COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 31-32 on south
boundary of township

CORNER MONUMENT Set 1" pipe with 4" Aluminum cap

DATE MONUMENT PLACED AND WITNESSED 10/25/62

WITNESSES TO CORNER.....



10" W. Birch - N11E - 16.6 ft

8" W. Birch - N64W - 21.1 ft

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established while making a survey in this area. Unable to locate anything for US evidence or a previous corner. Set corner at US record west of closing corner of Sections 5-6, on line over said corner and 1/4 corner east. This conforms almost exactly for proportionate measurement, and also places corners of Section 31 nearly on line. Checks swamp edge east very well.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Ostling* DATE 11/5/62
REGISTERED LAND SURVEYOR