

**SURVEY & REMONUMENTATION**

*Water*

MAY 05 1997

**RE MONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

RECEIVED FOR RECORD

96 NOV 25 PM 1:03

*J. J. Gray*  
CLERK/REGISTER  
CHEBOYGAN COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

For corners in Cheboygan (County) Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey T 34N R 1W M-3  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Brian K. Fullford, in a field survey on August, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

|    |    |   |    |   |    |   |    |   |    |   |    |   |   |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 10 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

A. Description of original monument and accessories and/or subsequent restoration:

|                         |                             |                            |
|-------------------------|-----------------------------|----------------------------|
| G.L.O.                  | 1951 D.O.C. Corner Record   | 1973 Recorded Survey       |
| Set Section Corner      | Dean DeLamater #5778        | Liber 343, Pages 450 & 451 |
| 8" Beech S31°W 9 Links  | Set 1" Pipe w/4" Brass Cap  | Delmer Porter #15410       |
| 7" Beech N12°E 18 Links | 8" H. Maple N70°W 26 Links  | Fnd Conservation Monument  |
|                         | 7" H. Maple S33°E 103 Links | 8" H. Maple N80°E 21.30'   |
|                         |                             | 12" H. Maple N65°W 16.22'  |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fnd 1" Pipe With Department of Conservation Brass Cap  
 Fnd 8" H. Maple N71°W 17.03' (DeLamater Witness)  
 Fnd 8" H. Maple N83°E 21.50' (Porter Witness)  
 Fnd 5" Maple S66°W 2.05' (Porter Tag)

LIBER 010 PAGE 205



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-3 Fnd 1" Pipe with 4" Department of Conservation Brass Cap. Accepted as a careful & faithful re-establishment of the position of the original corner.

21" Maple N40°E 23.90' Set Tag  
 9" Maple Clump N83°E 21.90' Set Tag  
 5" Maple S66°W 2.05' Tag #15410  
 8"/12" Tw. Maple N71°W 17.03' Set Tag

*Marcus A. Ray*



THIS CORNER IS ALSO DESIGNATED AS CORNER CODE #A-3, IN T34N-R1E.

Signed by *Brian K. Fullford* 41099  
 Surveyor's Michigan License No. Brian K. Fullford, PS

Date 10/22/96