

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 34 N. R. 1 W. ●	J-3
2. PROPERTY CONTROLLING IN SECTION 2 _____	T. 34 N. R. 1 W. ●	12, 15, 16
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on December 8, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- J-3 This corner reset to proper location at midpoint on line, from erroneous 1951 position.
- 12 Set by standard survey procedure for the subdivision of sections.
- 15 Set by standard survey procedure for the subdivision of sections.
- 16 Set by standard survey procedure for the subdivision of sections.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

	12	15
Reset DNR mon. & red-top post	Set 3/8" hex rod & post	Set 3/8" hex rod & post
8" Birch S65°W 12.3	6" Cedar N50°E 3.4	12" Twin Maple N39°W 22.2
5" Balsam N08°W 43.9	6" Cedar S03°E 10.05	10" Maple S78°E 46.3
	16	
	Set 3/8" hex rod & post	
	4" Balsam S15°W 11.45	
	4" Maple N62°E 7.85	


SIGNED BY *Kenneth J. Ostling* DATE 12-15-76

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____ CHEBOYGAN COUNTY