

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD


T. 34 N.R. 1 W
T 33 NR 1 W Cheboygan COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 34-3

CORNER MONUMENT Set 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 10/15/62

WITNESSES TO CORNER.....



6" H. Maple	-	S76E	-	36.9 ft
9" H. Maple	-	S62W	-	17.5 ft

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement, midpoint on line, between section corners while making a survey in this ~~area~~ area. Could find no previous corner and no positive original evidence. Falls near center of E-W fireline.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Ostling* DATE 11/5/62
REGISTERED LAND SURVEYOR