

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 34 N R. 1 W


Cheboygan COUNTY

DESCRIPTION OF CORNER 1/4 Corner common to Sections 28-29

CORNER MONUMENT Set 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED June 17, 1966

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

10" Cedar S 84 E 56.0'

10" Cedar S 75 W 74.2'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found while making a retracement in this township. Found 1 1/2" pipe by Schaaf in place as established in 1930's. Both USBT stumps in place, the SW with lower good/face and excellent scribe marks.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Ostling* DATE June 20, 1966
REGISTERED LAND SURVEYOR #10068