

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 34 N.R. 1 W


Cheboygan COUNTY

DESCRIPTION OF CORNER 1/4 corner common to sections 24-25

CORNER MONUMENT Set 1" pipe with 4" Aluminum cap

DATE MONUMENT PLACED AND WITNESSED 8-31-66

WITNESSES TO CORNER.....



18" R. Pine N 30 W 16.7'

22' R. Pine S 60 E 22.5'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found during a survey in this township. Found very old squared post at corner, nearly on line but 25 links east of midpoint, between section' corners. One possible stump bottom for USBT.

SURVEYOR'S SEAL

SIGNED *Herbert J. Ostlund* DATE November 18, 1966
REGISTERED LAND SURVEYOR #10068